BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/RD/WORK_INDENT16738

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/09/2014-15, Date: 23.01.2015

Providing wet mix in cut portion roads in DEO Residency layout in ward no. 07.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of R SATHEESH	
				In Figures	In Words
1	48	KSRRB M300-2: Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 1.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3. p. no 138, i. no : 19.1, SR: 2014-15	cum	104.3	Rupees One Hundred Four and Thirty Paise Only
2	3466.4	KSRRB M300-52.1. Scarifying the existing granular road surface to a depth of 50mm and disposal of scarified material within all lifts and leads upto 1000 metres complete as per specifications.MORTH Specification No. 305.4.3 (P-144, Item No. 19.58 SR 2014-15)	Sqm	23.0	Rupees Twenty Three Only
3	3402	KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. (145, I.No. 19.64)	Sqm	5.0	Rupees Five Only
4	2007	KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. (P. 154 Item No. 20.18)	cum	1500.0	Rupees One Thousand Five Hundred Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92